



- NOTES:
- FOR PUMP SPECIFICATIONS REFER TO PUMP DESIGN BRIEF.
 - THE CONTRACTOR AND SUPPLIER SHALL COORDINATE POWER REQUIREMENTS PRIOR TO ORDERING OF THE PUMP STATION.
 - PER ONSITE SEPTIC SOLUTIONS, LLC (SUPPLIER), THE TOP OF THIS TANK SHALL BE BURIED NO DEEPER THAN 3 FEET BELOW FINISHED GRADE. IF A DEEPER BURIAL DEPTH IS NEEDED SEE SUPPLIER FOR SIMILAR TANKS THAT CAN BE BURIED DEEPER THAN 3 FEET.

SPECIAL NOTE:

- ALL PIPING WITHIN PUMP STATION AND VALVE PIT TO BE 2" SCH 80 PVC UNLESS OTHERWISE SPECIFIED

- SPECIFICATIONS:
- TANK TO MEET ASTM C1227-13 AND ASTM C890-13 REQUIREMENTS
 - MID SEAM CONSTRUCTION
 - JOINT SEALANT: 1" NOMINAL DIAMETER OR EQUIVALENT BUTYL RUBBER MASTIC SEALANT CONTINUOUS IN JOINT.
 - ALL DIMENSIONS SHOWN ARE PER ONSITE SEPTIC SOLUTIONS, LLC PRODUCTS 2017.

3,000 GALLON MID SEAM 6" TOP & BOTTOM PRECAST CONCRETE HEAVY DUTY DUPLEX PUMP STATION WITH VALVE PIT

1/2"=1'-0"



BUSINESS PARK AT CAMBRIDGE
CAMBRIDGE, VT. 05444
psl@onsitesepicsolutions.biz
TEL. 802-644-5500