



NOTES:

1. FOR PUMP SPECIFICATIONS REFER TO PUMP DESIGN BRIEF.
2. THE CONTRACTOR AND SUPPLIER SHALL COORDINATE POWER REQUIREMENTS PRIOR TO ORDERING OF THE PUMP STATION.
3. PER ONSITE SEPTIC SOLUTIONS, LLC (SUPPLIER), THE TOP OF THIS TANK SHALL BE BURIED NO DEEPER THAN 3 FEET BELOW FINISHED GRADE. IF A DEEPER BURIAL DEPTH IS NEEDED SEE SUPPLIER FOR SIMILAR TANKS THAT CAN BE BURIED DEEPER THAN 3 FEET.

SPECIAL NOTE:

1. ALL PIPING WITHIN PUMP STATION AND VALVE PIT TO BE 2" SCH 80 PVC UNLESS OTHERWISE SPECIFIED

SPECIFICATIONS:

1. TANK TO MEET ASTM C1227-13 AND ASTM C890-13 REQUIREMENTS
2. MID SEAM CONSTRUCTION
3. JOINT SEALANT: 1" NOMINAL DIAMETER OR EQUIVALENT BUTYL RUBBER MASTIC SEALANT CONTINUOUS IN JOINT.
4. ALL DIMENSIONS SHOWN ARE PER ONSITE SEPTIC SOLUTIONS, LLC PRODUCTS 2017.

3,000 GALLON MID SEAM 6" TOP & BOTTOM PRECAST CONCRETE HEAVY DUTY DUPLEX PUMP STATION

1/2"=1'-0"



BUSINESS PARK AT CAMBRIDGE
CAMBRIDGE, VT. 05444
paul@onsitesepticsolutions.biz
TEL. 802-644-5500